

***Addendum – RFP 2021-007 Route 40 Elementary Septic Field Replacement***

Contractor shall furnish and install a 10000-gallon septic tank in lieu of relocating existing tank. Contractor shall remove and dispose of the existing septic tank and siphon chamber. Contractor shall assume schools will be closed with minimal staff during construction. Should schools reopen during construction GCPS will work with the contractor to develop strategies for accommodating increased flow during the school day. Any additional work required as a result of schools opening will be at a negotiated cost to the owner.